

Builder/Developer Staking Requirements
NOVEC Requirements for Total Conduit Staking

- 1) The ground is graded to +/- 6" to Final Grade
- 2) The front and/or back of NOVEC's easement are staked.
 - ***** Stakes shall be marked and labeled as Front Stake or Back Stake depending on where it is located.
- 3) Lot corners are marked properly, staked or property pins installed.
- 4) All Building Corners are staked
- 5) All equipment locations are identified.
- 6) Minimum of two (2) front corners (Right Front Corner or Left Front Corner) of Transformers and Pedestals shall be staked.
- 7) All other equipment i.e. Enclosures, Pull Boxes shall have all four (4) corners staked.
- 8) All easement bump outs; corners and easement variables shall be staked front and back.
- 9) All stakes must be placed in the ground prior to scheduling a pre-construction walk thru.

Customer Requirements	
Specific Job Requirements	Conduit Inspection Requirements
	For job sites in Eastern Prince William County call: 703-392-1715
	For job sites North of Rt 50 Loudoun County call: 703-669-6070
	All other locations: call 703-754-6784
	NOVEC scheduler must be contacted two (2) working days prior to needing inspection.
	** See Electricians Guide, for access go to: www.novec.com/customer-service/new-construction-service/ then choose residential or commercial builder guidelines

Legend "Equipment/Material Not To Scale"

Existing	Proposed	Replace	Return	OH Primary/Secondary Conductor
●	○	⊗	⊙	Existing Install/Transfer
▲	△	⊗	⊙	Return
⊗	⊗	⊗	⊙	Spacer Cable 3-Phase Existing
⊗	⊗	⊗	⊙	UG Primary/Secondary Conductor
⊗	⊗	⊗	⊙	Existing Install/Transfer
⊗	⊗	⊗	⊙	Return
⊗	⊗	⊗	⊙	Abandon
⊗	⊗	⊗	⊙	Duct Bank
⊗	⊗	⊗	⊙	Existing Install/Transfer
⊗	⊗	⊗	⊙	Return/Remove
⊗	⊗	⊗	⊙	Street Lights
⊗	⊗	⊗	⊙	Existing Install/Transfer
⊗	⊗	⊗	⊙	Return/Remove
⊗	⊗	⊗	⊙	Fuse Bank
⊗	⊗	⊗	⊙	Existing Install/Transfer
⊗	⊗	⊗	⊙	Return/Remove
⊗	⊗	⊗	⊙	Replace



Project Data

Sub Station: _____ | Cir #: _____ | ADC Map # _____

GPIN# _____ | Co. Grid # _____ | Start _____

Device # _____ | UPLINE _____ | DOWNLINE _____

WORK DESCRIPTION: _____

Subdivision: _____ | 0100 | 0100

Location: 8072 E MAIN ST
MARSHALL, VA 20115-0000

Designer Name: mcoleman | Phone# _____

WR# 153301 | Date: 5/14/2018

NOT TO SCALE | Sheet ___ of ___

